



**KEY:-**

- Proposed footpath construction to be 225mm in depth. Wearing course - 25mm. Binder course - 50mm. Sub-base - 150mm. Total area = 338m<sup>2</sup> or 77m<sup>3</sup>.
- Proposed 80mm Inlay carriageway reinstatement. Total Area = 4m<sup>2</sup>.
- Proposed Corduroy paving slabs Total = 9m<sup>2</sup>.
- Proposed buff tactile paving slabs. Total = 3m<sup>2</sup>.
- Proposed concrete edging kerbs. Length = 96m.
- Proposed dropped kerbs. Length = 4m.
- Proposed transition kerbs. Length = 4m.
- Proposed topsoil & turf. Total = 57m<sup>2</sup>.
- Proposed Glasdon Glenwood 170 Post Total = 6 posts.
- Proposed signs & posts Total = 15 Signs & 6 posts.
- Existing lighting columns.

H:\CH-Minor Works\WORK LOCATIONS\PARISHES\Kenilworth\MWT21 098 Kenilworth Cycle Network - Minor Enhancements\5 Drawings\MWT21 098 Kenilworth Cycle Network - Minor Enhancements.dwg

**Warwickshire County Council**  
**TRANSPORT AND ECONOMY**

**Traffic & Road Safety**  
 Communities, Shire Hall Post Room  
 Warwick, CV34 4SP  
 Tel : 01926 410410

[www.warwickshire.gov.uk](http://www.warwickshire.gov.uk)  
<mailto:communities@warwickshire.gov.uk>

**NOTES**

Based on Ordnance Survey mapping with the permission of the Controller of HMSO  
 © Crown Copyright and database right 2011. Ordnance Survey 100019520.  
 All rights reserved.  
 Unauthorised reproduction infringes copyright and may lead to prosecution or civil proceedings.  
 Warwickshire County Council.

REV	DATE	BY	CHK	AMENDMENT
-	--/--/--	-	-	-
-	--/--/--	-	-	-
-	--/--/--	-	-	-
-	--/--/--	-	-	-
-	--/--/--	-	-	-

Drawing title  
**Kenilworth Cycle Network  
 Minor Enhancements  
 General Arrangement Plan  
 WARWICKSHIRE**

Project title  
**Kenilworth Town Council Funded**

Drawn by  
**CR**

Checked by  
**GS**

Date  
**October 2021**

Scale  
**1:200 @ A2**

Drawing number  
**MWT21/098/02**