



Key:	Works Area	Temporary Traffic Signal
	Closure	
	Vehicle Diversion Route	
	Foot Diversion Route	
	Cone	
	Datum Point	

Safety Information:	Min width of sideways safety zone (S)	0.5m	1.2m
Min length of baysways clearance (L)	0.5m	30m	
A423			

Site Information:	NSG	Local Authority	USN	Road Type	Works Location	Surveyed	Perm Signals
	Oxford Road Marton	Warrickshire	32800858	Single lane carriageway	Road Width N/A		

Chapter 8 details:

- Detail B**
- Single/Dual carriageway 40mph or less - 450mm traffic cones.
- Single/Dual carriageway 50mph or more - 750mm traffic cones.
- Notes:
 - 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3 (Appendix 1).
 - 2) 65 tapered line (TAS) lighting no relaxation shoulders - 1m cones will be required for both standard and relaxation works for lead tapers and the facing wall of lane changes.

- Detail C1**
- Single/Dual carriageway 40mph or less - 450mm traffic cones.
- Single/Dual carriageway 50mph or more - 750mm traffic cones.
- Notes:
 - 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3.

- Detail C2**
- Single carriageway 40mph or less - 450mm traffic cones.
- Single/Dual carriageway 50mph or more - 750mm traffic cones.
- Notes:
 - 1) During darkness, warning lights to BS EN 12352:2006 should be provided in accordance with Table A1.3.

Rev	Date	Comments	By	CHK
1				

Balfour Beatty

Living Places
Working in Partnership with

traffix

total traffic & event management solutions
Old Arden Brickworks | Biscanell | Shillai West Midlands | B82 0DY
t: +44 (0)800 819 8001 f: +44 (0)1915 442507
info@traffixuk.com | www.traffixuk.com

Project title:	Traffic Management
Drawing title:	Proposed Road Closure A423 Oxford Road Marton
Date:	02/05/2025
Drawn:	NTS
CM:	BN
Project Number:	002
Revision:	

This drawing is copyright & the property of Traffic & must not be copied in whole or in part without the written permission. Copyright is reserved. © The Contractor is to report all discrepancies & errors to the Contract Manager prior to works commencing.